	PCBU / EMPLOYER / COMPANY DETAILS		SWMS No:
	Name: Unique Building Services Pty Ltd		Revision No: 003
	Address: 23 Yazaki Way, Carrum Downs, Victoria 3201		Revision Date: 12/12/2023
	ABN: 62 086 537 279	Phone: 04	14826727
	Approved by:	Date:	
	Works Manager: Simon Blackburn	Mobile: 04	90540137
PROJECT DETAILS	CLIENT / PRINCIPAL CONTRACTOR DETAILS		
Name:	Name:	Date provi	ded to PC:
Address:	Contact:	Phone:	

WORK ACTIVITY

Control of hazards and risks associated with carpentry work carried out during the construction of residential and commercial premises.

SCOPE OF WORK COVERED BY THIS SAFE WORK METHOD STATEMENT

The Carpentry Work Safe Work Method Statement (SWMS) outlines the main hazards and risks including risks associated with the risk of falls, hazardous manual tasks, and operation of mobile plant and vehicles in workplaces where construction of residential and commercial premises is being undertaken.

The SWMS provides details of the health and safety precautions (including personal protective equipment requirements) to be observed when carrying out carpentry work on construction sites and in residential and commercial premises.

GENERAL INSTRUCTIONS FOR SAFE WORK METHOD STATEMENTS	SITE SPECIFIC CONSIDERATIONS
A safe work method statement (SWMS) must be prepared for any and all high risk construction work to be undertaken prior to the work commencing. All high risk construction work must be carried out in accordance with this SWMS.	NOTE: This is a generic SWMS. A generic SWMS may be prepared and used for high risk construction work activities that are carried out on a regular basis; however, the generic SWMS must be reviewed by the person carrying out the work to take into account the hazards and risks for the specific workplace and amend the SWMS
This SWMS must be kept and be available for inspection until the high risk construction work to which this SWMS relates is completed. If the SWMS is revised, all versions should be kept. If a notifiable incident occurs in relation to the high risk construction work in this SWMS, the SWMS must be kept for at least 2 years from the date of the notifiable incident.	as necessary for the site where the work is to be carried out, and complete details such as names and qualifications of workers who will carry out the work. All amendments to the SWMS must conform to regulatory
The PCBU or employer must ensure, so far as is reasonably practicable, that the information, training and instruction is provided in a way that is readily understandable by any person to whom it is provided.	must be recorded on the SWMS for that project or site. All workers are required to sign-off on the SWMS before the work is commenced.

Carpentry Work

WHAT MEASURES ARE IN PLACE TO ENSURE COMPLIANCE WITH THIS SWMS?					PERSON	RESPONSIBLE FOR MO	ONIT	ORING COMPLIANCE WITH	H THIS SWI	MS	
	Supervision	In	spections		Site audit	Name				Date Recei	ved
HOW WILL SWMS CONTROL MEASURES BE REVIEWED?				PERSON	RESPONSIBLE FOR RE	EVIE	W OF SWMS CONTROL ME	ASURES			
	Compliance with re	gulations & CoPs?	Fit for purpose	& adeo	quate for task?	Name				Date Recei	ved
HOW WILL CHANGES TO THIS SWMS BE MADE? HOW WILL CHANGES TO THIS SWMS BE COMMUNICATE						S BE COMMUNICATED TO	WORKERS	?			
	JSA (on site – approval required) Revision (revised SWMS re			/MS re-issued)		SWMS induction		Pre-start meeting		Toolbox talk	
		HIGH RISK C	ONSTRUCTION WO	RK AC	TIVITIES (CHECK	ANY THAT	ARE APPLICABLE TO) WC	ORK COVERED BY THIS	SWMS)	
	A risk of a person f	falling more than 2 metre	s (or 3 metres in SA)		Demolition of a load-bearing structure			Work on a telecommunications tower			
	Work in or near a s 1.5m; or in a tunne	shaft or trench with an ex	cavated depth over		Temporary load-bearing support structures Wor		Work on or near pressurised gas distribution mains or piping				
	Work in an area at a workplace in which there is any movement of powered mobile plant Work		Work involving the use of explosives			Work on or near chemical, fuel or refrigerant lines		gerant lines			
	The disturbance of or likely disturbance of asbestos Tilt-up or preca		Tilt-up or precast con	Filt-up or precast concrete Work in an area in which		Work in an area in which th	h there are artificial extremes of temperature				
			ent to a road, railway, shipping lane or used by traffic other than pedestrians Work on, under or near water or other liquid that involves a drowning		liquid that involves a risk of						
	Work carried out in or near a confined space			Work in an area that may have a contaminated or flammable atmosphere			Diving work				

RISK CONTROL	Actions to be taken to control risks		
Hierarchy of risk controls (in order of preference)	How will risk controls be implemented?		
1 Elimination (most effective)	Eliminate the hazard and the associated risk		
2 Substitution	Substitute the hazard with something safer		
3 Isolation	Isolate the hazard from people (e.g., barrier, wall)		
4 Engineering means	Physical controls including guards, mechanical devices		
5 Administrative controls	Work methods or procedures to minimise exposure		
6 PPE (least effective)	Provide protective clothing and equipment to workers		

What measures are in place to ensure compliance with this SWMS?	Check
Check all measures used to ensure compliance with this SWMS	
Responsible person appointed to monitor compliance with SWMS by workers	
Site-specific inductions; pre-start meetings and toolbox talks with workers	
SWMS provided to and discussed with workers and signed off	
Ongoing workplace supervision by competent personnel	
Monitoring of work methods and review of SWMS where necessary	
SWMS control measures revised if work methods or risks change	

Carpentry Worl	k
-----------------------	---

REQUIRED PLANT / TOOLS / EQUIPMENT	SAFETY INSPECTIONS & MAINTENANCE		CHEMIC	CALS TO BE	USED ON SITE		
			Name of chemical	Hazar	d class (GHS)	Category	SDS date
		-					
		-					
			PERMITS, ISOLATIC	ONS AND AU	THORISATIONS	REQUIRED	

HIGH RISK WORK LICENSES AND COMPETENCIES REQUIRED							
Plant or occupation	Class	Type/description	Worker's name	Number	Expiry		

Carpentry Work

SAFETY EQUIPMENT REQUIRED						
Barricading, traffic control devices	Signage	Fall prevention (safety harness, lanyard)	Traffic control	Other (specify below):		
PERSONAL PROTECTIVE CLOTHING AND EQUIPMENT (PPE)						
Required PPE is highlighted in red with green check. Optional PPE is highlighted in blue. Ensure all workers have required PPE before any work requiring the PPE has commenced.						



WORKER INSTRUCTION & SIGN OFF

All workers must sign below before commencing work covered by this SWMS: I have been consulted, instructed in and fully understand the content of this SWMS

	Signature	Date
	Image: state	Image: space

	REVIEWS						
Review No.	01	02	03	04	05	06	
Name							
Signature							
Date							

Job activity	Hazards and associated risks	How will the hazards and the risks be controlled?
Inductions and training	Untrained workers	All persons working on a construction site must hold a General Construction Induction (GCI) card. Carry out site-specific inductions for all workers. All workers must be competent in the tasks carried out. Vehicles, plant and equipment must only be operated by licensed or competent persons. Workers must be trained in the correct selection, use and care of PPE including fit-checking of respiratory protection.
Site security	Unauthorised entry to site	Provide security fence, safety barricades, etc., around work site, and post warning signs at entrances to site. All plant, materials and tools must be inside secure areas. Site must be secured from entry when unattended.
Electrical hazards	Electrocution	All electrical work will be carried out only by licensed or registered electrical workers. Ensure that safety switch is provided on switchboard, and check operation before connecting leads to board.
	Electrical tools and equipment	All electric tools and equipment will be inspected, tested and tagged every 3 months and before use on construction work. Inspect tools and check operation of controls daily before use. Faulty electric tools will not be used. Keep electric leads off ground to protect from damage.
	Overhead electricity lines	Maintain safe approach distance from energised electricity cables when erecting or working on scaffolds. Consult supply authority if work carried out will be placed at risk due to presence of electricity installations.
Storage and handling of materials	Personal injury	Wear gloves to prevent hand injuries when handling timber, concrete and metal materials. Provide assistance or use mechanical aids to carry and move heavy items.

Carpentry Work

Job activity	Hazards and associated risks	How will the hazards and the risks be controlled?	
Hazardous manual tasks	Strains, personal injury	Provide sufficient personnel or mechanical aids to handle and move large, heavy or awkward loads. Provide safe means of transporting and moving loads on site to minimise manual movement of heavy items Provide manual handling training to all persons.	
Work at heights - Fall prevention	Personal injury; death	Provide safe means of access to and for working at heights and where a person may fall from one level to another.	
	Scaffolds	Erection of tower and mobile scaffolds using modular scaffolding must be carried out by a competent person. All scaffolds from which a person or object can fall more than 4 metres must be erected, altered and dismantled by or under the direct supervision of a licensed scaffolder. All scaffolds are to be erected in accordance with supplier of manufacturer's instructions.	
Use of power tools	Electric shock	Inspect leads and plug for damage, and ensure that a current test tag is attached to the plug end of leads of all power tools. Inspect tools before use. Check casing for damage, cracks and missing screws; ensure that all guards are fitted and controls operate smoothly. Do not use faulty or out-of-test tools or equipment. Wear eye and hearing protection when using power tools such as saws, and when working in areas where saws are used	
	Rotating tools	Secure loose clothing and dangling jewellery and contain long hair and beards when using rotating tools.	
Hand tools	Personal injury	Inspect hand tools before use – ensure that handles are not loose or damaged, and that tool is in good condition for use. Do not use hand tools for any purpose other than that for which they were designed.	

Carpentry Work

Job activity	Hazards and associated risks	How will the hazards and the risks be controlled?	
Nailing tools	Noise	Inspect tool for damage, and ensure that it is in good working order. Check that the tool is correctly and securely connected to the air hose.	
		Check operation of all controls and safeguards before loading fasteners.	
	Flying objects	Restrict entry into work area to those persons involved in nailing only.	
		Never point a nailing tool at another person – never assume tool is empty.	
		Never drive fasteners into knots in timber or on top of other fasteners - always ensure that fasteners will be driven into a solid, sound backing.	
		"Bump fire" guns must not be used on ladders or other elevated areas.	
		Wear eye and hearing protection when using nailing tools and other air powered tools.	
Formwork and boxing	Hazardous manual tasks	Keep timber and stays for formwork and boxing clear of other work areas and materials.	
		Obtain assistance when carrying and placing long pieces of timber.	
		Avoid working in bent position for long periods when fixing forms and boxing.	
		Remove all nails and clean and oil forms and timber boxing immediately following stripping.	
Erection of framing	Risk of falls	Ensure that work area is clear of obstacles that may create a trip hazard while handling and erecting frames.	
		Provide adequate edge protection where risk of a fall from any height is present.	
Erection of trusses	Risk of falls	Provide a safe working platform or access for persons working at heights. Ensure that adequate edge protection or other fall prevention system is implemented.	
Fixing of sheeting Hazardous manual tasks Obtain assistance when fixing sheeting to external walls.		Obtain assistance when fixing sheeting to external walls.	
		Always work from a stable work platform at heights.	
		Pre-cut sheets to size on ground where possible.	
		Avoid fixing wall sheeting in windy or gusty conditions.	

Job activity	Hazards and associated risks	How will the hazards and the risks be controlled?		
	Fixing internal sheeting	Obtain assistance or use lifting aids when fixing sheets.		
Site clean-up and waste disposal	Slips, trips and falls of persons	Ensure that all scrap and waste material is removed and that area is clear of obstacles. Check safety of area before removing barricading.		

Carpentry Work

SAFE WORK METHOD STATEMENT

JSA (ADDITIONAL SITE-SPECIFIC HAZARDS & RISKS OR CONTROLS NOT INCLUDED ELSEWHERE IN SWMS)						
Job activity	Hazards / associated risks	How will the hazards and the risks be controlled?	Approved by			